

PLANILLA DE DOBLADO DE HIERROS

Pos.	Ubicación	diam. (mm)	sep. (cm)	long. (m)	cantid.	long. Total (m)	peso (kg)	Doblado
1	losa levantados (EXTREMAS O SIMPLE)	12	21,0	3,86	70	270,03	239,62	
2	losa rectos (EXTREMAS O SIMPLES)	12	21,0	3,75	70	262,50	232,93	
	repartición losa principal	8	20,0	7,36	40	294,40	116,11	
3	tabiques estribos	8	10,5	4,82	58	279,56	110,25	
4	tabiques estribos	8	10,5	5,14	58	298,12	117,57	
3 m	tabiques estribos (hierros 3 en long. m)	10	10,5	4,88	94	458,72	282,67	
4 m	tabiques estribos (hierros 4 en long. m)	12	10,5	5,26	94	494,44	438,75	

PLANILLA DE DOBLADO DE HIERROS

Pos.	Ubicación	diam. (mm)	sep. (cm)	long. (m)	cantid.	long. Total (m)	peso (kg)	Doblado
	Repartición en estribos	8	20	7,76	92	713,92	281,56	
5	zapata estribos inferiores	10	16,0	1,06	100	106,00	65,32	
6	zapata estribos superiores	8	20,0	1,26	80	100,80	39,75	
	repartición zapata estribos	8		7,76	16	124,16	48,97	
	repartición zapata pilas centrales	8		7,36	8	58,88	23,22	
7 y 8	pilas centrales	8	20,0	5,17	76	392,92	154,96	
	Repartición en pilas	8	20,0	7,36	46	338,56	133,52	

PLANILLA DE DOBLADO DE HIERROS

Pos.	Ubicación	diam. (mm)	sep. (cm)	long. (m)	cantid.	long. Total (m)	peso (kg)	Doblado
9	zapata pila central inferiores	8	20,0	0,71	37	26,27	10,36	
10	zapata pila central superiores	8	20,0	0,89	37	32,93	12,99	
11	armaduras y refuerzos de alas	12	29,0	3,08	64	197,12	174,92	
12	armaduras y refuerzos de alas	12	29,0	2,28	56	127,68	113,30	
13	armaduras y refuerzos de alas	12	29,0	2,45	56	137,20	121,75	
14	armaduras y refuerzos de alas	12	29,0	9,15	32	292,80	259,82	

PLANILLA DE DOBLADO DE HIERROS

Pos.	Ubicación	diam. (mm)	sep. (cm)	long. (m)	cantid.	long. Total (m)	peso (kg)	Doblado
17	armadura vereda	8		1,53	78	119,66	47,19	
18	Pilar baranda	8		1,80	24	43,20	17,04	
19	Baranda	12		3,46	24	83,04	73,69	
	Estribos pilares y baranda	6	15,0	0,40	188	75,31	16,71	
20	Vereda repartición	8		3,46	12	41,52	16,37	
21	pasadores entre losas y estribos	10	15,0	0,25	98	24,50	15,10	
	repartición en alas (longitud promedio)	8	20,0	4,16	80	332,80	131,25	